60006669

Mining District File Summary Sheet

DISTRICT	Rosebud
DIST_NO	4010
COUNTY If different from written on document	Pershing
TITLE If not obvious	Rosebud Drill Hole File - Hole No D-184-98
AUTHOR	K. Allen; S. King
DATE OF DOC(S)	1998
MULTI_DIST Y / (N?) Additional Dist_Nos:	
QUAD_NAME	Sulphur 7.5'
P_M_C_NAME (mine, claim & company names)	Rosebud Mine, Hecla Mining Co, Rosebud Project Rosebud Mining Co., LLC
COMMODITY If not obvious	gold; silver
NOTES	drill logs; assay; geology; photographs; receipts; total depth 80' handwritten notes down hole camera images 15 p. 3 down hole camera images

Keep docs at about 250 pages if no oversized maps attached
(for every 1 oversized page (>11x17) with text reduce
the amount of pages by ~25)

	Initials	Date
SS:	DD	4/28/08
DB:		
SCANNED:		

Revised: 1/22/08

D-184-98

6000 0669
4010

6600 6669

quartz, chalcedony, silicification
faults, fractures
FeOx BARITE
sulfide
calcite, carbonate
argillization, white clays
propylitization
potassic alteration
chlorite, chloritic clays

Hecla MINING COMPANY

ROSEBUD PROJECT
DIAMOND DRILL LOG

HOLE NUMBER D-184-98 | LOCATION EAST, ACCESS 43 | REMARKS
PAGE 1 OF 2 | NORTHING
DATE 2/24/98 | EASTING
LOGGED BY HBM | ELEVATION
SCALE 1"=10' | AZIMUTH N54W
TOTAL DEPTH 80' | INCLINATION +75

ITH.	OX/RED.	LITHOLOGY	FT	GRAPHIC LOG	STRUCTURE	ALTERATION AND MINERALIZATION
0'-44.1 DOZER	0-80' REDUCED	0'-~16.5': AUTOBXAT'D LT. GRAY APHANITIC DOZER. FROM 6.6' TEXTURE IS HIGHLITED WITH FAINT RUDDY FeOx STAINING. ~16.5'-36.3': MASSIVE APHANITIC GREY DOZER, LOCALLY MOTTLED (PSEUDOBRECCIATED) WITH FAINT RUDDY FeOx STAINING. LOCALLY FLOW BANDING IS PICKED OUT BY FeOx STAINING. 36.3'-44.1': CATACLASTIC/WKLY MYLONITIC TEXTURE IN OTHERWISE MASSIVE GRY-BUFF DOZER TO CONTACT. TIGHTLY-PACKED FINELY BRECCIATED DOZER IS DENSELY STOCKWORKED TO CRACKLE BRECCIATED WITH ~~#~~ WAXY YELLOW-GRN CLAY VNLTS. 44.1-45.0': DOZER IN SILICIFIED FAULT ZONE. MYLONITIC TEXTURE FOUND ABOVE CONTINUES BUT IS OVERPRINTED BY SILICA VEINING & 2NDARY CATACLASTIC BRECCIA IMMEDIATELY BELOW SILICA-PYRITE VEIN/JNT SLIP PLANE AT 44.1'. 45': BUFF-GRY SILICA-FLOODED DOZER GIVES WAY TO GRN CLAY ALTERED, SILICA-FLOODED BUD-DERIVED (?) MUSH.	0 10 20 30 40 50		0-21': STRONGLY BROKEN THROUGHOUT. MOD. JNTING 5-~12': INTERMITTENT NARROW ZONES OF WK MILLING. 12.3-14.3': WEAK MILLING OF DOZER. NOW SEMI-HEALED. STRONGLY BROKEN ROCK. 44.1-45': SILICIFIED FLT BXA IN DOZER.	0-5.5': MOD. QUARTZ+ MARCASITE VNING. TR. TO MOD. CLAY ALTN IN WALL-ROCK. 5.5-6.6': STRONG SILICA BXA # VEINS +/- WK MARCASITE. 6.6-13': MOD. QUARTZ + MARCASITE VNLTS. TR. TO MOD. WALLROCK ARGILLIZATION. ~13'-16.5': STR. SILICA +/- MARCASITE VNING, MOD. ARGILLIZATION OF WALLROCK. DULL BRASSY FG PY OR MARC BLEEDS INTO WALLROCK OFF VNLTS ⇒ MOD. PY BLEBBING. 16.5'-34.8': MOD. QUARTZ+ MARCASITE VNLTS. MOD. DISS'D PYRITIC BLEBS OFF VNS. 34.8-35.3': 6" WIDE WHT CLAY + BLOCKY BARITE VN. EARLIER SILICA + MARC AT RIMS. 40.5' - CONTACT': MOD. BLK-GRY SILICA-SULFIDE MICROBRECCIA VNLTS. 44.1-45.0': CLAY-STOCKWK BXA FROM ABOVE IS OVERPRINTED BY PERVASIVE SILICIFICATION. TEXTURE DESTRUCTIVE AT CONTACT.
44.1-80.0 SOUTH RIDGE FAULT						

ANALYTICAL DATA

FROM	TO	W	Au	Ag	Au2	Ac
0	5.2					
5.2	7.6					
7.6	12.3					
12.3	16.7					
16.7	20.5					
20.5	24.7					
24.7	30.0					
30.0	34.8					
34.8	36.8					
36.8	40.3					
40.3	44.1					
44.1	45.1					
45.1	47.1					
47.1	49.2					

HOLE NUMBER D-184-98 PAGE 2 OF 2

ITH.	OX/RED.	LITHOLOGY	FT	GRAPHIC LOG	STRUCTURE	ALTERATION AND MINERALIZATION
		47.1'-49.2': NEAR TOTAL REPLACEMENT WITH GREY SILICA. ORIGINAL BRECCIA TEXTURE IS LARGELY DESTROYED. 53.5': PIMA. 49.2-55.3': HETEROLITHIC, MATRIX-SUPPORTED FAULT BRECCIA. MATRIX ROCK FLOUR IS INTENSELY FLOODED WITH GREY SILICA. PARTIAL TEXTURE DESTRUCTION. VERY POORLY SORTED FRAGMENTS RANGING FROM COBBLE TO PEBBLE-SIZED, SUB-ANGULAR TO SUB-ROUNDED. MAIN LITH. TYPES =1) DULL DARK FLESH COLORED, APHANITIC GROUNDMASS PROBABLY PLAG-BEARING PORPHYRY, 2) DK GRN SPECKLED GRN CLAY ALTERED BUD. 3) EARLIER BRECCIAS., 55.3-64.0': BUD FRAGMENTS IN SLIGHTLY LIGHTER GRN, MUSHY BUD-DERIVED MATRIX, ~~HERE~~ SPOTTILY MOD. TO TRACE SILICIFIED. GRY SILICA VNING MODERATE, FOUND AS PERVASIVE SILICIFICATION WANES. 64.0-66.0': HETEROLITHIC MATRIX-SUPPORTED FAULT BXA LIKE THAT SEEN FROM 49.2-54.3'. GREY SILICA FLOODED MATRIX. 66.0-68.3': ANHEDRAL BARITE +/- STIBNITE CRACKLE BRECCIA CEMENT TO STOCKWORK, IN GRNISH-GRY SILICA-FLOODED FAULT BRECCIA(?) MOD. TO STR. TEXTURE DESTRUCTION.	50 60 70 80		49.2-55.3': MATRIX-SUPPORTED HETEROLITHIC BRECCIA, ~80 DOMINATED BY FLESH-COLORED, PLAG-BEARING, ANGULAR FRAGMTS. 60 STIBNITE 55.3-64': TECTONIZED GRN MUSH - SOME DKER GRN BUD(?) FRAGMTS. 64.0-68.3': MATRIX-SUPPORTED HETEROLITHIC FAULT BXA. FROM 68.3': GRADATIONAL DECREASE IN TECTONIZATN & HYDROTHERMAL OVERPRINT. STILL IN FAULT ZONE TO T.D. DECREASING FRAGMENT CONTENT, MORE IDENTIFIABLE BUD TEXTURE DOWNHOLE.	47.1-49.2': TOTAL SILICA REPLACEMT. WK MARC. 49.2-51.5': SOLID SILICA FLOODING OF MATRIX, W/ SIGNIFICANT TEXTURE DESTRUCTION. WK MARC. 51.5'-55.3': VUGGY TEXTURE-DESTRUCTIVE GRY SILICA IN MATRIX. WHT CLAY + STIBNITE +/- BARITE VUG FILL. MOD. DISS'D MARC. 55.3-64': PERVASIVE GRN CLAY ALT'N, STR. SILICA VNING W/ LOCAL PERVASIVE SILICIFICATION. STR. L. BARITE + STIBNITE. MOD. DISS'D MARC W/ PY OVERGROWTH. 64.0'-66.0': STR. PERVASIVE GRY SILICA IN MATRIX. DK SILICA-SULFIDE VNLTS. 66.0'-68.3': SEMI-HEALED Ba CRACKLE BXA IN GRY SILICA-FLOODED ROCK. 68.3'-81': MOD/STR PERVASIVE SILICA DECREASES
		T.D. 81' 68.3'-~79': DECREASING BARITE +/- STIBNITE VNING IN MOD'LY TO STR'LY SILICIFIED GRN-GRY UBUD DERIVED FAULT BXA. PERVASIVE SILICA V. GRADUALLY DECREASING DOWNHOLE. GRADES INTO GRAY DIFFUSE SILICA VEINING 79-81': DECREASING TEXTURE-DESTRUCTIVE PERVASIVE SILICA. DARKER GRN CLAY ALTERATION. MODERATE VUGGYNESS, FILLED WITH BARITE +/- STIBNITE & MINOR WHT CLAY.				

ANALYTICAL DATA						
FROM	TO	W	Au	Ag	Au2	
49.2	52.1					
52.1	55.3					
55.3	58.5					
58.5	64.0					
64.0	66.0					
66.0	68.3					
68.3	71.0					
71.0	74.9					
74.9	79.0					
79.0	81.0					

HECLA MINING COMPANY – ROSEBUD PROJECT
GEOTECHNICAL DRILL LOG

HOLE # D-184-98 DATE: 12/24/98 LOGGED BY: HBM PAGE 1 OF 2

DRILL RUN		SOLID CORE RECOVERY (%)	TOTAL CORE RECOVERY (%)	ROD	ROCK STRENGTH		FRACTURE DATA				DENSITY DATA			
FROM	TO				DOWNHOLE DEPTH	POINT LOAD INDEX (psi)	FRACTURE DENSITY/FT.	AVG. ANGLE TO C.A.	ROUGHNESS	INFILL	DOWNHOLE DEPTH	SAMPLE WEIGHT (g)	DISPLACEMENT (cc)	DENSITY (g/cc)
0	5.0	92.0	92.0	0										
5.0	8.0	90.0	90.0	0										
8.0	13.0	92.0	92.0	24.0										
13.0	18.0	96.0	96.0	0										
18.0	23.0	106.0	106.0	26.0										
23.0	28.0	90.0	90.0	44.0										
28.0	33.0	101.0	101.0	32.0										
33.0	38.0	101.0	101.0	66.0										
38.0	43.0	104.0	104.0	34.0										
43.0	48.0	106.0	106.0	80.0										
48.0	53.0	90.0	90.0	50.0										

HECLA MINING COMPANY – ROSEBUD PROJECT
GEOTECHNICAL DRILL LOG

HOLE # D-184-98 DATE: 02/24/98 LOGGED BY: KBM PAGE 2 OF 2

DRILL RUN		SOLID CORE RECOVERY (%)	TOTAL CORE RECOVERY (%)	ROD	ROCK STRENGTH		FRACTURE DATA				DENSITY DATA			
FROM	TO				DOWNHOLE DEPTH	POINT LOAD INDEX (psi)	FRACTURE DENSITY/FT.	AVG. ANGLE TO C.A.	ROUGHNESS	INFILL	DOWNHOLE DEPTH	SAMPLE WEIGHT (g)	DISPLACEMENT (cc)	DENSITY (g/cc)
53.0	58.0	102.0	102.0	64.0										
58.0	63.0	98.0	98.0	80.0										
63.0	66.0	99.0	99.0	26.0										
66.0	71.0	94.0	94.0	44.0										
71.0	76.0	100.0	100.0	80.0										
76.0	81.0	96.0	96.0	54.0										
	T.D.													

AMERICAN ASSAY LABORATORIES

PROVISIONAL REPORT SP048249

PO BOX 11530
RENO NV.USA
Ph.(702) 356-0506, Fax.(702) 356-1413

HECLA MINING COMPANY

COPIES TO : KURT ALLEN

:

:

:

CLIENT REFERENCE No: D-187-98 RECEIVED : 5 MAR 1998

No. SAMPLES : 25 REPORTED : 13 MAR 1998

MAIN SAMPLE TYPE : DRILL CORE

NEVADA LEGISLATIVE DISCLAIMER :-
The results of this assay were based solely upon the content of the sample submitted. Any decision to invest should be made only after the potential investment value of the claim or deposit has been determined based on the results of assays of multiple samples of geological materials collected by the prospective investor or by a qualified person selected by him and based on an evaluation of all engineering data which is available concerning any proposed project.

ANALYSIS	ANALYTICAL METHOD	QUALITY PARAMETER	UNIT	DETECTION
Au(OZ)	FA30	15%	OPT	0.001
Au(RZ)	FA30	15%	OPT	0.001
AuGRAV	GRAV	15%	OPT	0.001
Ag(OZ)	D210	10%	OPT	0.02

SIGNATORY : Susan King M.S.

03/13/1998 10:48 7023561413 AMERICAN ASSAY LABS PAGE 04

AMERICAN ASSAY LABORATORIES

PROVISIONAL REPORT SP04R249

CLIENT : HECLA MINING COMPANY
PROJECT : ROSEBUD DEVELOPMENT
REFERENCE : D-187-98

REPORTED : 13 MAR 1998

SAMPLES	Au(OZ)	Au(RZ)	AuGRAV	Ag(OZ)
D-184-98 0.0-5.2	0.018	0.019		
D-184-98 5.2-7.6 2.4	0.415		0.461	
D-184-98 7.6-12.3 4.7	0.042	0.044		
D-184-98 12.3-16.7 4.4	0.170		0.202	
D-184-98 16.7-20.5	0.097		0.097	
D-184-98 20.5-24.7	0.090		0.072	
D-184-98 24.7-30.0	0.006			
D-184-98 30.0-34.8	0.019			
D-184-98 34.8-36.8	0.068		0.076	
D-184-98 36.8-40.3	0.002			
D-184-98 40.3-44.1	0.009			
D-184-98 44.1-45.1	0.033			
D-184-98 45.1-47.1	0.165		0.134	
D-184-98 47.1-49.2	0.022			
D-184-98 49.2-52.1	0.002			
D-184-98 52.1-55.3	0.006			
D-184-98 55.3-58.5	0.003			
D-184-98 58.5-64.0	0.004	0.004		
D-184-98 64-66	0.013			
D-184-98 66.0-68.3	0.002			
D-184-98 68.3-71.0	0.002			
D-184-98 71.0-74.9	0.002			
D-184-98 74.9-79	0.002			
D-184-98 79-81	0.003			
27753	0.520			

5.2'-16.7' = 11.5' @ 0.169 Au 0.22 Ag

2' @

PAGE 05 AMERICAN ASSAY LABS 7023501413 10:40 03/13/1998

American Assay Laboratories

INVOICE

Remit To: P.O. Box11530
Reno, Nevada 89510
Phone NO.: 702-356-0606
Fax No.: 702-356-1413

AMERICAN ASSAY LABORATORIES
1500 GLENDALE AVE.
SPARKS, NV 89431

(702) 356-0606

INVOICE NO: SP 0048249-IN
INVOICE DATE: 03/17/98

INVOICE TO:
THE ROSEBUD MINING CO., LLC
HECLA MINING COMPANY, OPERATOR
P.O. BOX 2610
WINNEMUCCA NV 89446

THE ROSEBUD MINING CO., LLC
HECLA MINING COMPANY, OPERATOR
P.O. BOX 2610
WINNEMUCCA NV 89446

CUSTOMER P.O.	PROJECT	TERMS
D-187-98	DEVELOPMENT	NET 30 - DUE IN U.S. DOLLARS

QUANTITY	DESCRIPTION	PRICE	AMOUNT
25	SAMPLES RECEIVED	.00	.00
24	JAW CRUSHING CHARGE	1.30	31.20
24	COARSE MILLING CHARGE	4.50	108.00
24	SPLITTING CHARGE	2.40	57.60
24	RING MILLING CHARGE	2.00	48.00
25	Au (1 A.T. FIRE ASSAY)	8.00	200.00
6	Au ANALYSES/GRAVIMETRIC	8.75	52.50
25	HYDROCHLORIC/NITRIC DIGESTION	2.00	50.00
25	Ag ANALYSES	1.00	25.00
1	Ag (ore grade) ANALYSES	5.00	5.00

86-5110-477
CDA

NET INVOICE:	577.30
LESS DISCOUNT:	115.46
FREIGHT:	.00
INVOICE TOTAL:	461.84

xAMERICAN ASSAY LABORATORIES

ANALYSIS REPORT SP048249

American Assay Laboratories

PO BOX 11530
RENO NV,USA
Ph.(702) 356-0606, Fax.(702) 356-1413

HECLA MINING COMPANY

COPIES TO : KURT ALLEN

:

:

:

CLIENT REFERENCE No: D-187-98

No. SAMPLES : 25

MAIN SAMPLE TYPE : DRILL CORE

RECEIVED : 5 MAR 1998

REPORTED : 16 MAR 1998

NEVADA LEGISLATIVE DISCLAIMER :-
The results of this assay were based solely upon the content of the sample submitted. Any decision to invest should be made only after the potential investment value of the claim or deposit has been determined based on the results of assays of multiple samples of geological materials collected by the prospective investor or by a qualified person selected by him and based on an evaluation of all engineering data which is available concerning any proposed project.

ANALYSIS	ANALYTICAL METHOD	QUALITY PARAMETER	UNIT	DETECTION
Au(OZ)	FA30	15%	OPT	0.001
Au(RZ)	FA30	15%	OPT	0.001
AuGRAV	GRAV	15%	OPT	0.001
Ag(OZ)	D210	10%	OPT	0.02

SIGNATORY : Susan King M.S.

AMERICAN ASSAY LABORATORIES

ANALYSIS REPORT SP048249

American Assay Laboratories

CLIENT : HECLA MINING COMPANY
PROJECT : ROSEBUD DEVELOPMENT
REFERENCE : D-187-98

REPORTED : 16 MAR 1998

SAMPLES	Au(OZ) FA30 OPT	Au(RZ) FA30 OPT	AuGRAV GRAV OPT	Ag(OZ) D210 OPT
D-184-98 0.0-5.2	0.018	0.019		0.08
D-184-98 5.2-7.6	0.415		0.461	0.57
D-184-98 7.6-12.3	0.042	0.044		0.11
D-184-98 12.3-16.7	0.170		0.202	0.15
D-184-98 16.7-20.5	0.097		0.097	0.08
D-184-98 20.5-24.7	0.090		0.072	0.12
D-184-98 24.7-30.0	0.006			0.05
D-184-98 30.0-34.8	0.019			0.05
D-184-98 34.8-36.8	0.068		0.076	0.14
D-184-98 36.8-40.3	0.002			0.04
D-184-98 40.3-44.1	0.009			0.05
D-184-98 44.1-45.1	0.033			0.07
D-184-98 45.1-47.1	0.165		0.134	0.04
D-184-98 47.1-49.2	0.022			0.05
D-184-98 49.2-52.1	0.002			0.10
D-184-98 52.1-55.3	0.005			0.14
D-184-98 55.3-58.5	0.003			1.67
D-184-98 58.5-64.0	0.004	0.004		0.18
D-184-98 64-66	0.013			0.34
D-184-98 66.0-68.3	0.002			0.85
D-184-98 68.3-71.0	0.002			0.17
D-184-98 71.0-74.9	0.002			0.32
D-184-98 74.9-79	0.002			0.08
D-184-98 79-81	0.003			0.33
27753	0.520			5.07

xAMERICAN ASSAY LABORATORIES

ANALYSIS REPORT SP048249

American Assay Laboratories

PO BOX 11530
RENO NV,USA
Ph.(702) 356-0606, Fax.(702) 356-1413

HECLA MINING COMPANY

COPIES TO : KURT ALLEN

:

:

:

CLIENT REFERENCE No: D-187-98 RECEIVED : 5 MAR 1998

No. SAMPLES : 25 REPORTED : 16 MAR 1998

MAIN SAMPLE TYPE : DRILL CORE

NEVADA LEGISLATIVE DISCLAIMER :-
The results of this assay were based solely upon the content of the sample submitted. Any decision to invest should be made only after the potential investment value of the claim or deposit has been determined based on the results of assays of multiple samples of geological materials collected by the prospective investor or by a qualified person selected by him and based on an evaluation of all engineering data which is available concerning any proposed project.

ANALYSIS	ANALYTICAL METHOD	QUALITY PARAMETER	UNIT	DETECTION
Au(OZ)	FA30	15%	OPT	0.001
Au(RZ)	FA30	15%	OPT	0.001
AuGRAV	GRAV	15%	OPT	0.001
Ag(OZ)	D210	10%	OPT	0.02

SIGNATORY : Susan King M.S.

AMERICAN ASSAY LABORATORIES

ANALYSIS REPORT SP048249

American Assay Laboratories

CLIENT : HECLA MINING COMPANY
PROJECT : ROSEBUD DEVELOPMENT
REFERENCE : D-187-98

REPORTED : 16 MAR 1998

SAMPLES	Au(OZ) FA30 OPT	Au(RZ) FA30 OPT	AuGRAV GRAV OPT	Ag(OZ) D210 OPT
D-184-98 0.0-5.2	0.018	0.019		0.08
D-184-98 5.2-7.6	0.415		0.461	0.57
D-184-98 7.6-12.3	0.042	0.044		0.11
D-184-98 12.3-16.7	0.170		0.202	0.15
D-184-98 16.7-20.5	0.097		0.097	0.08
D-184-98 20.5-24.7	0.090		0.072	0.12
D-184-98 24.7-30.0	0.006			0.05
D-184-98 30.0-34.8	0.019			0.05
D-184-98 34.8-36.8	0.068		0.076	0.14
D-184-98 36.8-40.3	0.002			0.04
D-184-98 40.3-44.1	0.009			0.05
D-184-98 44.1-45.1	0.033			0.07
D-184-98 45.1-47.1	0.165		0.134	0.04
D-184-98 47.1-49.2	0.022			0.05
D-184-98 49.2-52.1	0.002			0.10
D-184-98 52.1-55.3	0.005			0.14
D-184-98 55.3-58.5	0.003			1.67
D-184-98 58.5-64.0	0.004	0.004		0.18
D-184-98 64-66	0.013			0.34
D-184-98 66.0-68.3	0.002			0.85
D-184-98 68.3-71.0	0.002			0.17
D-184-98 71.0-74.9	0.002			0.32
D-184-98 74.9-79	0.002			0.08
D-184-98 79-81	0.003			0.33
27753	0.520			5.07

SP

SUBMITTAL FORM

American Assay Laboratories

Geochemical • Environmental • Metallurgical

Sparks Office
1500 Glendale Ave.
Nevada 89431
Box 11530
Reno, NV 89510
Telephone
(702) 356-0606
Fax
(702) 356-1413

Tucson Office
2775 E. Ganley
Tucson, AZ 85706
Telephone
(520) 294-8078
Fax
(520) 294-6352

Elko Office
2320 Last Chance Rd.
Nevada 89801
Box 2908
Elko, NV 89801
Telephone
(702) 738-9100
Fax
(702) 738-2594

Mazatlan Office
Telephone/Fax
011-52-69-170035

Other Offices
Lima, Peru
Santiago, Chile
Mendoza, Argentina

Company: ROSEBUD MINING CO. LLT

Address: P.O. BOX 2610

City WINNEMUCCA State NV Zip 89446

Telephone Number: (702) 623-6912 Fax Number: (702) 623-6967

Project Name: DEVELOPMENT Purchase Order Number:

Date Submitted: 03/04/98 Number of Samples: 24

RESULTS REPORTED IN: ppm [ ] ppb [ ] opt [X]

D-184-98 SAMPLE IDENTIFICATION		TYPE	ELEMENTS REQUIRED
0-5.2	52.1-55.3	CORE	AU-AG ACCORDING TO
5.2-7.6	55.3-58.5		ROSEBUD MINE PROTOCOL
7.6-12.3	58.5-64.0		
12.3-16.7	64.0-66.0		
16.7-20.5	66.0-68.3		
20.5-24.7	68.3-71.0		
24.7-30.0	71.0-74.9		
30.0-34.8	74.9-79.0		
34.8-36.8	79.0-81.0		
36.8-40.3			
40.3-44.1			
44.1-45.1			
45.1-47.1			
47.1-49.2			
49.2-52.1			

COARSE REJECTS (Normally Discarded After 60 Days)

[ ] Return COD after analysis complete

PULPS (Normally Stored Free For One Month)

[ ] Discard after one month
[ ] Return COD after one month

RESULTS AND INVOICES TO BE SENT TO:

Invoice to:

KURT ALLEN

Results to:

KURT ALLEN

Comments:

CLIENT FILE COPY

Down-Hole Survey Dec. 15. 7

Hole #	Depth	Bearing	Dip	True Bearing	True Dip
D-184-98	Collar	S 73.5°E	44.5°	N 57.8°W	45.5°
	40′	S 74.0°E	44.5°	N 58.3°W	45.5°
	81′	S 73.5°E	~~44.5~~ 44.0°	N 57.8°W	46.0°

D-184-98 BOX NO 2
DEPTH 9.5 - 20.5
19
13
16.7
12.3

D-184-98 BOX NO 1
DEPTH 0.0 - 9.5
15.2
7.6
5
8

D-184-98 BOX NO 3
DEPTH 20.5 - 29.
20.5
23
24.7
25


47.1
44.1
40.3
D-184-98 BOX NO 5
DEPTH 38.5 - 47.5


34.8
30.0
33
36.8
D-184-98 BOX NO 4
DEPTH 29. - 38.5


49.2
52.5
55.3
D-184-98 BOX NO 6
DEPTH 47.5 - 57.

71
68.5
D-184-98 BOX NO 8
DEPTH 66. - 75.5

66
64.0
56
63
58.5
D-184-98 BOX NO 7
DEPTH 57. - 66.


76.
78.0
81
D-184-98 BOX NO 9
DEPTH 75.5 - 81.

S 40 E
S 50 E
S 40 E
S 50 E

50
SE
40
SE
6
30
SE
8